



# 舗装工

## 数量集計表

名称	区分	単位	数量	備考
工事延長		m	323	
【舗装工】				
表層	t=3cm	m <sup>2</sup>	1,560	1,573.63 - 6.18 = 1,567.45
不陸整正 粒度調整碎石(M-30)	t=3cm	m <sup>2</sup>	1,560	
【舗装準備工】				
舗装版切断工 アスファルト	t=3cm	m	39	39.0
舗装版切断工 コンクリート	t=10cm	m	28	28.3
【舗装版撤去工】				
舗装版取壊し工	t=3cm	m <sup>2</sup>	1,560	
【構造物撤去工】				
アスファルト殻運搬・処分工		m <sup>3</sup>	47	1,567.5 × 0.03 = 47.0235

## 出野広野線舗装工事

## 舗 装 工

測 点	単距離	舗 装 工							
		表 層							
		断 面(m)	平均	数 量(m <sup>2</sup> )					
NO. 21		4.40							
NO. 21+16.4	16.400	4.20	4.30	70.52					
		5.40							
NO. 22	3.600	7.00	6.20	22.32					
NO. 22+3.0	3.000	6.20	6.60	19.80					
		5.20							
NO. 22+7.3	4.300	5.50	5.35	23.01					
NO. 23	12.700	3.60	4.55	57.79					
NO. 24	20.000	3.20	3.40	68.00					
NO. 25	20.000	3.40	3.30	66.00					
NO. 26	20.000	4.80	4.10	82.00					
NO. 27	20.000	5.40	5.10	102.00					
NO. 28	20.000	6.10	5.75	115.00					
NO. 29	20.000	4.20	5.15	103.00					
NO. 29+1.2	1.200	4.50	4.35	5.22					
NO. 29+6.0	4.800	10.30	7.40	35.52					
NO. 30	14.000	3.70	7.00	98.00					
NO. 30+9.9	9.900	3.90	3.80	37.62					
		4.50							
NO. 30+15.7	5.800	7.00	5.75	33.35					
NO. 31	4.300	4.50	5.75	24.73					
NO. 32	20.000	4.50	4.50	90.00					
NO. 33	20.000	4.50	4.50	90.00					
NO. 34	20.000	4.50	4.50	90.00					
NO. 35	20.000	4.50	4.50	90.00					
NO. 35+4.0	4.000	5.80	5.15	20.60					
		7.20							
NO. 36	16.000	8.20	7.70	123.20					
NO. 37+6.0		4.40							
NO. 38	14.000	4.50	4.45	62.30					
NO. 38+9.0	9.000	5.20	4.85	43.65					
計	323.000			1573.63					







### 構造物延長集計表

側点	延長	側点	延長
防護柵工			
左側			
Gr-C-4E			
No.30 付近	13		
No.31 付近	17		
	30		