



# 土 工 計 算 書

測点	距離 (m)	床堀(土砂)			残土処理								
		断面積(m <sup>2</sup> )	平均	数量(m <sup>3</sup> )	断面積(m <sup>2</sup> )	平均	数量(m <sup>3</sup> )	断面積(m <sup>2</sup> )	平均	数量(m <sup>3</sup> )	断面積(m <sup>2</sup> )	平均	数量(m <sup>3</sup> )
NO. 0		1.5			0.5								
NO. 1	20.00	2.2	1.85	37.00	0.7	0.60	12.00						
NO. 2	20.00	2.2	2.20	44.00	0.7	0.70	14.00						
NO. 3	20.00	2.2	2.20	44.00	0.7	0.70	14.00						
NO. 4	20.00	2.1	2.15	43.00	0.7	0.70	14.00						
NO. 5	20.00	2.3	2.20	44.00	0.7	0.70	14.00						
NO. 6	20.00	3.2	2.75	55.00	1.1	0.90	18.00						
NO. 7	20.00	2.2	2.70	54.00	0.7	0.90	18.00						
NO. 7	0.00	1.9			0.7								
NO. 8	20.00	1.3	1.60	32.00	0.5	0.60	12.00						
NO. 9	20.00	2.0	1.65	33.00	0.7	0.60	12.00						
NO. 10	20.00	1.7	1.85	37.00	0.6	0.65	13.00						
NO. 11	20.00	2.0	1.85	37.00	0.7	0.65	13.00						
NO. 12	20.00	2.0	2.00	40.00	0.7	0.70	14.00						
NO. 13	20.00	2.0	2.00	40.00	0.7	0.70	14.00						
NO. 14	20.00	1.9	1.95	39.00	0.7	0.70	14.00						
NO. 14 + 1.5	1.50	1.9	1.90	2.85	0.7	0.70	1.05						
合 計				581.85			197.05						

## 舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(4cm)			上層路盤(8cm)			下層路盤(10cm)		
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 0		4.40			4.40			4.40			4.40		
NO. 0 + 0.7	0.70	4.19	4.30	3.01	4.19	4.30	3.01	4.19	4.30	3.01	4.19	4.30	3.01
NO. 0 + 0.7		5.64			5.64			5.64			5.64		
NO. 0 + 3.9	3.20	4.71	5.18	16.56	4.71	5.18	16.56	4.71	5.18	16.56	4.71	5.18	16.56
NO. 0 + 11.4	7.50	5.25	4.98	37.35	5.25	4.98	37.35	5.25	4.98	37.35	5.25	4.98	37.35
NO. 0 + 14.4	3.00	5.13	5.19	15.57	5.13	5.19	15.57	5.13	5.19	15.57	5.13	5.19	15.57
NO. 0 + 16.4	2.00	6.00	5.57	11.13	6.00	5.57	11.13	6.00	5.57	11.13	6.00	5.57	11.13
NO. 0 + 16.4		5.00			5.00			5.00			5.00		
NO. 1	3.60	4.27	4.64	16.69	4.27	4.64	16.69	4.27	4.64	16.69	4.27	4.64	16.69
NO. 1 + 4.2	4.20	4.46	4.37	18.33	4.46	4.37	18.33	4.46	4.37	18.33	4.46	4.37	18.33
NO. 1 + 7.4	3.20	4.62	4.54	14.53	4.62	4.54	14.53	4.62	4.54	14.53	4.62	4.54	14.53
NO. 1 + 13.1	5.70	4.24	4.43	25.25	4.24	4.43	25.25	4.24	4.43	25.25	4.24	4.43	25.25
NO. 2	6.90	4.19	4.22	29.08	4.19	4.22	29.08	4.19	4.22	29.08	4.19	4.22	29.08
NO. 2 + 10.7	10.70	4.40	4.30	45.96	4.40	4.30	45.96	4.40	4.30	45.96	4.40	4.30	45.96
NO. 3	9.30	4.31	4.36	40.50	4.31	4.36	40.50	4.31	4.36	40.50	4.31	4.36	40.50
NO. 3 + 5.6	5.60	4.57	4.44	24.86	4.57	4.44	24.86	4.57	4.44	24.86	4.57	4.44	24.86
NO. 3 + 10.2	4.60	4.32	4.45	20.45	4.32	4.45	20.45	4.32	4.45	20.45	4.32	4.45	20.45
NO. 4	9.80	3.99	4.16	40.72	3.99	4.16	40.72	3.99	4.16	40.72	3.99	4.16	40.72
NO. 4 + 16.9	16.90	3.80	3.90	65.83	3.80	3.90	65.83	3.80	3.90	65.83	3.80	3.90	65.83
小計				425.81			425.81			425.81			425.81

(水戸小由里線)

数計-02

## 舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(4cm)			上層路盤(8cm)			下層路盤(10cm)		
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 4 + 16.9		4.40			4.40			4.40			4.40		
NO. 5	3.10	4.32	4.36	13.52	4.32	4.36	13.52	4.32	4.36	13.52	4.32	4.36	13.52
NO. 5 + 10.0	10.00	4.39	4.36	43.55	4.39	4.36	43.55	4.39	4.36	43.55	4.39	4.36	43.55
NO. 5 + 10.0		4.87			4.87			4.87			4.87		
NO. 5 + 11.6	1.60	5.19	5.03	8.05	5.19	5.03	8.05	5.19	5.03	8.05	5.19	5.03	8.05
NO. 5 + 11.6		6.04			6.04			6.04			6.04		
NO. 5 + 15.0	3.40	6.65	6.35	21.57	6.65	6.35	21.57	6.65	6.35	21.57	6.65	6.35	21.57
NO. 6	5.00	6.20	6.43	32.13	6.20	6.43	32.13	6.20	6.43	32.13	6.20	6.43	32.13
NO. 6 + 2.1	2.10	5.10	5.65	11.87	5.10	5.65	11.87	5.10	5.65	11.87	5.10	5.65	11.87
NO. 6 + 7.6	5.50	4.20	4.65	25.58	4.20	4.65	25.58	4.20	4.65	25.58	4.20	4.65	25.58
NO. 7	12.40	4.13	4.17	51.65	4.13	4.17	51.65	4.13	4.17	51.65	4.13	4.17	51.65
NO. 7 + 8.6	8.60	4.20	4.17	35.82	4.20	4.17	35.82	4.20	4.17	35.82	4.20	4.17	35.82
NO. 7 + 11.5	2.90	3.14	3.67	10.64	3.14	3.67	10.64	3.14	3.67	10.64	3.14	3.67	10.64
NO. 8	8.50	2.80	2.97	25.25	2.80	2.97	25.25	2.80	2.97	25.25	2.80	2.97	25.25
NO. 8 + 7.9	7.90	3.00	2.90	22.91	3.00	2.90	22.91	3.00	2.90	22.91	3.00	2.90	22.91
NO. 8 + 11.2	3.30	3.58	3.29	10.86	3.58	3.29	10.86	3.58	3.29	10.86	3.58	3.29	10.86
NO. 9	8.80	4.19	3.89	34.19	4.19	3.89	34.19	4.19	3.89	34.19	4.19	3.89	34.19
NO. 10	20.00	3.61	3.90	78.00	3.61	3.90	78.00	3.61	3.90	78.00	3.61	3.90	78.00
NO. 11	20.00	4.30	3.96	79.10	4.30	3.96	79.10	4.30	3.96	79.10	4.30	3.96	79.10
小計				504.66			504.66			504.66			504.66

## 舗装工数量計算書

測点	距離 (m)	不陸整正			車道表層(4cm)			上層路盤(8cm)			下層路盤(10cm)		
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 11		4.30			4.30			4.30			4.30		
NO. 11 + 8.0	8.00	4.32	4.31	34.48	4.32	4.31	34.48	4.32	4.31	34.48	4.32	4.31	34.48
NO. 11 + 10.2	2.20	4.66	4.49	9.88	4.66	4.49	9.88	4.66	4.49	9.88	4.66	4.49	9.88
NO. 11 + 15.8	5.60	4.59	4.63	25.90	4.59	4.63	25.90	4.59	4.63	25.90	4.59	4.63	25.90
NO. 12	4.20	4.16	4.38	18.38	4.16	4.38	18.38	4.16	4.38	18.38	4.16	4.38	18.38
NO. 13	20.00	4.19	4.18	83.50	4.19	4.18	83.50	4.19	4.18	83.50	4.19	4.18	83.50
NO. 14	20.00	4.01	4.10	82.00	4.01	4.10	82.00	4.01	4.10	82.00	4.01	4.10	82.00
NO. 14 + 1.5	1.50	3.96	3.99	5.98	3.96	3.99	5.98	3.96	3.99	5.98	3.96	3.99	5.98
小計				260.11			260.11			260.11			260.11
合計				1190.58			1190.58			1190.58			1190.58

## 舗装工数量計算書

測点	距離 (m)	路床安定処理(35cm)			路床安定処理(30cm)								
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 0		4.40											
NO. 0 + 0.7	0.70	4.19	4.30	3.01									
NO. 0 + 0.7		5.64											
NO. 0 + 3.9	3.20	4.71	5.18	16.56									
NO. 0 + 11.4	7.50	5.25	4.98	37.35									
NO. 0 + 14.4	3.00	5.13	5.19	15.57									
NO. 0 + 16.4	2.00	6.00	5.57	11.13									
NO. 0 + 16.4		5.00											
NO. 1	3.60	4.27	4.64	16.69									
NO. 1 + 4.2	4.20	4.46	4.37	18.33									
NO. 1 + 7.4	3.20	4.62	4.54	14.53									
NO. 1 + 13.1	5.70	4.24	4.43	25.25									
NO. 2	6.90	4.19	4.22	29.08									
NO. 2 + 10.7	10.70	4.40	4.30	45.96									
NO. 3	9.30	4.31	4.36	40.50									
NO. 3 + 5.6	5.60	4.57	4.44	24.86									
NO. 3 + 10.2	4.60	4.32	4.45	20.45									
NO. 4	9.80	3.99	4.16	40.72									
NO. 4 + 16.9	16.90	3.80	3.90	65.83									
小計				425.81			0.00						

## 舗装工数量計算書

測点	距離 (m)	路床安定処理 (35cm)			路床安定処理 (30cm)								
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 4 + 16.9		4.40											
NO. 5	3.10	4.32	4.36	13.52									
NO. 5 + 10.0	10.00	4.39	4.36	43.55									
NO. 5 + 10.0		4.87											
NO. 5 + 11.6	1.60	5.19	5.03	8.05									
NO. 5 + 11.6		6.04											
NO. 5 + 15.0	3.40	6.65	6.35	21.57									
NO. 6	5.00	6.20	6.43	32.13									
NO. 6 + 2.1	2.10	5.10	5.65	11.87									
NO. 6 + 7.6	5.50	4.20	4.65	25.58									
NO. 7	12.40	4.13	4.17	51.65	4.13								
NO. 7 + 8.6	8.60				4.20	4.17	35.82						
NO. 7 + 11.5	2.90				3.14	3.67	10.64						
NO. 8	8.50				2.80	2.97	25.25						
NO. 8 + 7.9	7.90				3.00	2.90	22.91						
NO. 8 + 11.2	3.30				3.58	3.29	10.86						
NO. 9	8.80				4.19	3.89	34.19						
NO. 10	20.00				3.61	3.90	78.00						
NO. 11	20.00				4.30	3.96	79.10						
小計				207.90			296.76						

## 舗装工数量計算書

測点	距離 (m)	路床安定処理 (35cm)			路床安定処理 (30cm)								
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 11					4.30								
NO. 11 + 8.0	8.00				4.32	4.31	34.48						
NO. 11 + 10.2	2.20				4.66	4.49	9.88						
NO. 11 + 15.8	5.60				4.59	4.63	25.90						
NO. 12	4.20				4.16	4.38	18.38						
NO. 13	20.00				4.19	4.18	83.50						
NO. 14	20.00				4.01	4.10	82.00						
NO. 14 + 1.5	1.50				3.96	3.99	5.98						
小計				0.00			260.11						
合計				633.71			556.87						





## As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 0		4.40											
NO. 0 + 0.7	0.70	4.19	4.30	3.01									
NO. 0 + 0.7		5.64											
NO. 0 + 3.9	3.20	4.71	5.18	16.56									
NO. 0 + 11.4	7.50	5.25	4.98	37.35									
NO. 0 + 14.4	3.00	5.13	5.19	15.57									
NO. 0 + 16.4	2.00	6.00	5.57	11.13									
NO. 0 + 16.4		5.00											
NO. 1	3.60	4.27	4.64	16.69									
NO. 1 + 4.2	4.20	4.46	4.37	18.33									
NO. 1 + 7.4	3.20	4.62	4.54	14.53									
NO. 1 + 13.1	5.70	4.24	4.43	25.25									
NO. 2	6.90	4.19	4.22	29.08									
NO. 2 + 10.7	10.70	4.40	4.30	45.96									
NO. 3	9.30	4.31	4.36	40.50									
NO. 3 + 5.6	5.60	4.57	4.44	24.86									
NO. 3 + 10.2	4.60	4.32	4.45	20.45									
NO. 4	9.80	3.99	4.16	40.72									
NO. 4 + 16.9	16.90	3.80	3.90	65.83									
小計				425.81									

## As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )	長さ(m)	平均	数量(m <sup>2</sup> )
NO. 4 + 16.9		4.40											
NO. 5	3.10	4.32	4.36	13.52									
NO. 5 + 10.0	10.00	4.39	4.36	43.55									
NO. 5 + 10.0		4.87											
NO. 5 + 11.6	1.60	5.19	5.03	8.05									
NO. 5 + 11.6		6.04											
NO. 5 + 15.0	3.40	6.65	6.35	21.57									
NO. 6	5.00	6.20	6.43	32.13									
NO. 6 + 2.1	2.10	5.10	5.65	11.87									
NO. 6 + 7.6	5.50	4.20	4.65	25.58									
NO. 7	12.40	4.13	4.17	51.65									
NO. 7 + 8.6	8.60	4.20	4.17	35.82									
NO. 7 + 11.5	2.90	3.14	3.67	10.64									
NO. 8	8.50	2.80	2.97	25.25									
NO. 8 + 7.9	7.90	3.00	2.90	22.91									
NO. 8 + 11.2	3.30	3.58	3.29	10.86									
NO. 9	8.80	4.19	3.89	34.19									
NO. 10	20.00	3.61	3.90	78.00									
NO. 11	20.00	4.30	3.96	79.10									
小計				504.66									



