

舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(5cm)								
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 32 + 4.4		8.30			8.30								
NO. 33 + 15.5	31.10	8.30	8.30	258.13	8.30	8.30	258.13						
NO. 34 + 5.5	10.00	7.00	7.65	76.50	7.00	7.65	76.50						
NO. 34 + 13.4	7.90	8.00	7.50	59.25	8.00	7.50	59.25						
NO. 35 + 9.3	15.90	8.00	8.00	127.20	8.00	8.00	127.20						
NO. 35 + 10.2	0.90	9.00	8.50	7.65	9.00	8.50	7.65						
NO. 35 + 17.3	7.10	9.00	9.00	63.90	9.00	9.00	63.90						
NO. 35 + 18.7	1.40	8.00	8.50	11.90	8.00	8.50	11.90						
NO. 37 + 0.1	21.40	8.00	8.00	171.20	8.00	8.00	171.20						
NO. 37 + 11.0	10.90	7.00	7.50	81.75	7.00	7.50	81.75						
NO. 50 + 10.0	259.00	7.00	7.00	1813.00	7.00	7.00	1813.00						
NO. 51 + 6.7	16.70	7.35	7.18	119.82	7.35	7.18	119.82						
NO. 51 + 7.4	0.70	8.36	7.86	5.50	8.36	7.86	5.50						
NO. 51 + 19.1	11.70	8.50	8.43	98.63	8.50	8.43	98.63						
NO. 51 + 19.9	0.80	7.50	8.00	6.40	7.50	8.00	6.40						
NO. 52 + 3.0	3.10	7.50	7.50	23.25	7.50	7.50	23.25						
NO. 52 + 4.4	1.40	7.76	7.63	10.68	7.76	7.63	10.68						
NO. 52 + 14.2	9.80	8.75	8.26	80.90	8.75	8.26	80.90						
NO. 53 + 2.0	7.80	9.09	8.92	69.58	9.09	8.92	69.58						
小計				3085.24			3085.24						

舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(5cm)								
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 53 + 2.0		9.09			9.09								
NO. 53 + 7.1	5.10	9.34	9.22	47.00	9.34	9.22	47.00						
NO. 53 + 12.6	5.50	9.17	9.26	50.90	9.17	9.26	50.90						
NO. 53 + 19.8	7.20	8.50	8.84	63.61	8.50	8.84	63.61						
NO. 54 + 8.7	8.90	7.50	8.00	71.20	7.50	8.00	71.20						
NO. 55 + 5.5	16.80	7.00	7.25	121.80	7.00	7.25	121.80						
NO. 56 + 0.8	15.30	7.50	7.25	110.93	7.50	7.25	110.93						
NO. 58 + 7.3	46.50	7.50	7.50	348.75	7.50	7.50	348.75						
NO. 58 + 9.1	1.80	8.50	8.00	14.40	8.50	8.00	14.40						
NO. 59 + 0.9	11.80	8.23	8.37	98.71	8.23	8.37	98.71						
NO. 59 + 1.3	0.40	7.21	7.72	3.09	7.21	7.72	3.09						
NO. 59 + 7.6	6.30	7.00	7.11	44.76	7.00	7.11	44.76						
NO. 61 + 13.8	46.20	7.00	7.00	323.40	7.00	7.00	323.40						
NO. 61 + 19.7	5.90	8.55	7.78	45.87	8.55	7.78	45.87						
NO. 63 + 15.0	35.30	8.43	8.49	299.70	8.43	8.49	299.70						
NO. 64	5.00	7.50	7.97	39.83	7.50	7.97	39.83						
NO. 64 + 4.8	4.80	7.50	7.50	36.00	7.50	7.50	36.00						
NO. 64 + 19.9	15.10	7.31	7.41	111.82	7.31	7.41	111.82						
NO. 65 + 8.0	8.10	7.00	7.16	57.96	7.00	7.16	57.96						
小計				1889.71			1889.71						

舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(5cm)								
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 65 + 8.0		7.00			7.00								
NO. 65 + 10.4	2.40	8.00	7.50	18.00	8.00	7.50	18.00						
NO. 66 + 2.2	11.80	8.00	8.00	94.40	8.00	8.00	94.40						
NO. 66 + 3.4	1.20	7.00	7.50	9.00	7.00	7.50	9.00						
NO. 67 + 13.1	29.70	7.00	7.00	207.90	7.00	7.00	207.90						
NO. 67 + 14.6	1.50	8.00	7.50	11.25	8.00	7.50	11.25						
NO. 69 + 3.1	28.50	8.00	8.00	228.00	8.00	8.00	228.00						
NO. 69 + 6.8	3.70	7.00	7.50	27.75	7.00	7.50	27.75						
NO. 72 + 16.8	70.00	7.00	7.00	490.00	7.00	7.00	490.00						
NO. 74 + 15.5	38.70	8.00	7.50	290.25	8.00	7.50	290.25						
NO. 81 + 9.8	134.30	8.00	8.00	1074.40	8.00	8.00	1074.40						
NO. 82 + 3.2	13.40	7.00	7.50	100.50	7.00	7.50	100.50						
NO. 84 + 0.3	37.10	7.00	7.00	259.70	7.00	7.00	259.70						
NO. 84 + 1.6	1.30	8.00	7.50	9.75	8.00	7.50	9.75						
NO. 84 + 11.1	9.50	8.00	8.00	76.00	8.00	8.00	76.00						
NO. 84 + 12.0	0.90	7.00	7.50	6.75	7.00	7.50	6.75						
NO. 85 + 16.5	24.50	7.00	7.00	171.50	7.00	7.00	171.50						
NO. 86 + 4.5	8.00	8.14	7.57	60.56	8.14	7.57	60.56						
NO. 86 + 19.9	15.40	8.66	8.40	129.36	8.66	8.40	129.36						
小計				3265.07			3265.07						

舗装工数量計算書

測点	距離 (m)	不陸修正			車道表層(5cm)								
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 86 + 19.9		8.66			8.66								
NO. 87 + 16.9	17.00	8.81	8.74	148.50	8.81	8.74	148.50						
NO. 88 + 10.0	13.10	7.69	8.25	108.07	7.69	8.25	108.07						
NO. 89 + 2.8	12.80	7.00	7.35	94.02	7.00	7.35	94.02						
NO. 90 + 10.4	27.60	7.00	7.00	193.20	7.00	7.00	193.20						
小計				543.79			543.79						
合計				8783.80			8783.80						

区画線工延長集計表

区画線工	延長(m)	区画線工	延長(m)
白色、破線、15cm			
NO. 34 + 13.4 ~ NO. 90 + 10.4	583.0		
白色、実線、15cm			
左側			
NO. 32 + 4.4 ~ NO. 34 + 13.4	49.0		
NO. 35 + 10.2 ~ NO. 51 + 7.4	317.2		
NO. 51 + 19.1 ~ NO. 58 + 9.1	130.0		
NO. 59 + 0.9 ~ NO. 65 + 10.4	129.5		
NO. 66 + 2.2 ~ NO. 84 + 1.6	359.4		
NO. 84 + 11.1 ~ NO. 90 + 10.4	119.3		
右側			
NO. 34 + 13.4 ~ NO. 90 + 10.4	1166.0		
合 計	2270.4		

舗装切断工延長集計表

舗装切断工	延長(m)	舗装切断工	延長(m)
アスファルト切断 (t=5cm)			
NO. 34 + 13.4 ~ NO. 37 + 0.1	45.4		
NO. 35 + 10.2 ~ NO. 35 + 17.3	7.7		
NO. 51 + 7.4 ~ NO. 51 + 19.1	11.8		
NO. 58 + 9.1 ~ NO. 59 + 0.9	11.6		
NO. 65 + 10.4 ~ NO. 66 + 2.2	11.9		
NO. 67 + 14.6 ~ NO. 69 + 3.1	28.9		
NO. 74 + 15.5 ~ NO. 81 + 9.8	133.7		
NO. 84 + 1.6 ~ NO. 84 + 11.1	9.5		
端部			
NO. 32 + 4.4	8.3		
NO. 90 + 10.4	7.5		
合 計	276.3		

As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 32 + 4.4		8.30											
NO. 33 + 15.5	31.10	8.30	8.30	258.13									
NO. 34 + 5.5	10.00	7.00	7.65	76.50									
NO. 34 + 13.4	7.90	8.00	7.50	59.25									
NO. 35 + 9.3	15.90	8.00	8.00	127.20									
NO. 35 + 10.2	0.90	9.00	8.50	7.65									
NO. 35 + 17.3	7.10	9.00	9.00	63.90									
NO. 35 + 18.7	1.40	8.00	8.50	11.90									
NO. 37 + 0.1	21.40	8.00	8.00	171.20									
NO. 37 + 11.0	10.90	7.00	7.50	81.75									
NO. 50 + 10.0	259.00	7.00	7.00	1813.00									
NO. 51 + 6.7	16.70	7.35	7.18	119.82									
NO. 51 + 7.4	0.70	8.36	7.86	5.50									
NO. 51 + 19.1	11.70	8.50	8.43	98.63									
NO. 51 + 19.9	0.80	7.50	8.00	6.40									
NO. 52 + 3.0	3.10	7.50	7.50	23.25									
NO. 52 + 4.4	1.40	7.76	7.63	10.68									
NO. 52 + 14.2	9.80	8.75	8.26	80.90									
NO. 53 + 2.0	7.80	9.09	8.92	69.58									
小計				3085.24									

As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 53 + 2.0		9.09											
NO. 53 + 7.1	5.10	9.34	9.22	47.00									
NO. 53 + 12.6	5.50	9.17	9.26	50.90									
NO. 53 + 19.8	7.20	8.50	8.84	63.61									
NO. 54 + 8.7	8.90	7.50	8.00	71.20									
NO. 55 + 5.5	16.80	7.00	7.25	121.80									
NO. 56 + 0.8	15.30	7.50	7.25	110.93									
NO. 58 + 7.3	46.50	7.50	7.50	348.75									
NO. 58 + 9.1	1.80	8.50	8.00	14.40									
NO. 59 + 0.9	11.80	8.23	8.37	98.71									
NO. 59 + 1.3	0.40	7.21	7.72	3.09									
NO. 59 + 7.6	6.30	7.00	7.11	44.76									
NO. 61 + 13.8	46.20	7.00	7.00	323.40									
NO. 61 + 19.7	5.90	8.55	7.78	45.87									
NO. 63 + 15.0	35.30	8.43	8.49	299.70									
NO. 64	5.00	7.50	7.97	39.83									
NO. 64 + 4.8	4.80	7.50	7.50	36.00									
NO. 64 + 19.9	15.10	7.31	7.41	111.82									
NO. 65 + 8.0	8.10	7.00	7.16	57.96									
小計				1889.71									

As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 65 + 8.0		7.00											
NO. 65 + 10.4	2.40	8.00	7.50	18.00									
NO. 66 + 2.2	11.80	8.00	8.00	94.40									
NO. 66 + 3.4	1.20	7.00	7.50	9.00									
NO. 67 + 13.1	29.70	7.00	7.00	207.90									
NO. 67 + 14.6	1.50	8.00	7.50	11.25									
NO. 69 + 3.1	28.50	8.00	8.00	228.00									
NO. 69 + 6.8	3.70	7.00	7.50	27.75									
NO. 72 + 16.8	70.00	7.00	7.00	490.00									
NO. 74 + 15.5	38.70	8.00	7.50	290.25									
NO. 81 + 9.8	134.30	8.00	8.00	1074.40									
NO. 82 + 3.2	13.40	7.00	7.50	100.50									
NO. 84 + 0.3	37.10	7.00	7.00	259.70									
NO. 84 + 1.6	1.30	8.00	7.50	9.75									
NO. 84 + 11.1	9.50	8.00	8.00	76.00									
NO. 84 + 12.0	0.90	7.00	7.50	6.75									
NO. 85 + 16.5	24.50	7.00	7.00	171.50									
NO. 86 + 4.5	8.00	8.14	7.57	60.56									
NO. 86 + 19.9	15.40	8.66	8.40	129.36									
小計				3265.07									

As 舗装取壊工数量計算書

測点	距離 (m)	As舗装取壊(t=5cm)											
		長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)	長さ(m)	平均	数量(m ²)
NO. 86 + 19.9		8.66											
NO. 87 + 16.9	17.00	8.81	8.74	148.50									
NO. 88 + 10.0	13.10	7.69	8.25	108.07									
NO. 89 + 2.8	12.80	7.00	7.35	94.02									
NO. 90 + 10.4	27.60	7.00	7.00	193.20									
小計				543.79									
合計				8783.80									

