

数 量 総 括 表

| 工 種 | 種 別 | 細 目 | 規 格 | 単 位 | 数 量 | 摘 要 |
|-----------|---------|----------------|-----------------|----------------|----------------|--------|
| 舗 装 工 | 車 道 舗 装 | 表層(切削オーバーレイ) | 再生密粒度アスコン t=3cm | m ² | 2956.2 | 数計-01 |
| | | | | m ² | | |
| 区 画 線 工 | 外 側 線 | 白線・実線・W=15cm | | m | 954.1 | 数計-05 |
| | 横断歩道 1 | W=45cm | | m | 25.1 | 数計-05 |
| | 横断歩道 2 | W=45cm | | m | 17.6 | 数計-05 |
| | 横断歩道 3 | W=45cm | | m | 18.0 | 数計-05 |
| | 停止線 1 | W=45cm | | m | 2.5 | 数計-05 |
| | 停止線 2 | W=45cm | | m | 2.3 | 数計-05 |
| | 停止線 3 | W=45cm | | m | 2.3 | 数計-05 |
| | 横断歩道予告 | W=30cm | 15cm換算値 | m | 99.1 | 数計-05 |
| | 破 線 1 | W=15cm, L=1.0m | | m | 16.0 | 数計-05 |
| | 破 線 2 | W=30cm, L=1.0m | | m | 16.0 | 数計-05 |
| | 構造物撤去工 | 舗装版切削 | t=3cm | | m ² | 2956.2 |
| A s 殻 処 分 | | | | m ³ | 88.7 | 数計-03 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

舗装工数量計算書

| 測点 | 距離 (m) | 車道切削オーバーレイ(3cm) | | | | | | | | | | | |
|-------|-----------|-----------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO.0 | | 5.51 | | | | | | | | | | | |
| NO.1 | 20.00 | 6.67 | 6.09 | 121.80 | | | | | | | | | |
| NO.2 | 20.00 | 5.00 | 5.84 | 116.70 | | | | | | | | | |
| NO.3 | 20.00 | 5.44 | 5.22 | 104.40 | | | | | | | | | |
| NO.4 | 20.00 | 5.28 | 5.36 | 107.20 | | | | | | | | | |
| NO.5 | 20.00 | 5.25 | 5.27 | 105.30 | | | | | | | | | |
| NO.6 | 20.00 | 5.19 | 5.22 | 104.40 | | | | | | | | | |
| NO.7 | 20.00 | 5.30 | 5.25 | 104.90 | | | | | | | | | |
| NO.8 | 20.00 | 5.27 | 5.29 | 105.70 | | | | | | | | | |
| NO.9 | 20.00 | 5.46 | 5.37 | 107.30 | | | | | | | | | |
| NO.10 | 20.00 | 5.29 | 5.38 | 107.50 | | | | | | | | | |
| NO.11 | 20.00 | 5.13 | 5.21 | 104.20 | | | | | | | | | |
| NO.12 | 20.00 | 5.27 | 5.20 | 104.00 | | | | | | | | | |
| NO.13 | 20.00 | 5.20 | 5.24 | 104.70 | | | | | | | | | |
| NO.14 | 20.00 | 5.38 | 5.29 | 105.80 | | | | | | | | | |
| NO.15 | 20.00 | 5.36 | 5.37 | 107.40 | | | | | | | | | |
| NO.16 | 20.00 | 5.33 | 5.35 | 106.90 | | | | | | | | | |
| NO.17 | 20.00 | 5.38 | 5.36 | 107.10 | | | | | | | | | |
| 小計 | | | | 1825.30 | | | 0.00 | | | 0.00 | | | 0.00 |

舗装工数量計算書

| 測点 | 距離 (m) | 車道切削オーバーレイ(3cm) | | | | | | | | | | | |
|------------|-----------|-----------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO.17 | | 5.38 | | | | | | | | | | | |
| NO.18 | 20.00 | 5.50 | 5.44 | 108.80 | | | | | | | | | |
| NO.19 | 20.00 | 5.58 | 5.54 | 110.80 | | | | | | | | | |
| NO.20 | 20.00 | 6.11 | 5.85 | 116.90 | | | | | | | | | |
| NO.21 | 20.00 | 5.24 | 5.68 | 113.50 | | | | | | | | | |
| NO.22 | 20.00 | 5.40 | 5.32 | 106.40 | | | | | | | | | |
| NO.23 | 20.00 | 6.15 | 5.78 | 115.50 | | | | | | | | | |
| NO.24 | 20.00 | 6.03 | 6.09 | 121.80 | | | | | | | | | |
| NO.25 | 20.00 | 5.71 | 5.87 | 117.40 | | | | | | | | | |
| NO.26 | 20.00 | 5.96 | 5.84 | 116.70 | | | | | | | | | |
| NO.26+17.7 | 17.70 | 5.58 | 5.77 | 102.13 | | | | | | | | | |
| NO.27 | 2.30 | 5.49 | 5.54 | 12.73 | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 小計 | | | | 1142.66 | | | | | | | | | |
| 合計 | | | | 2967.96 | | | 0.00 | | | 0.00 | | | |

舗装切削工数量計算書

| 測点 | 距離 (m) | アスファルト舗装切削(3cm) | | | | | | | | | | | |
|-------|-----------|-----------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO.0 | | 5.51 | | | | | | | | | | | |
| NO.1 | 20.00 | 6.67 | 6.09 | 121.80 | | | | | | | | | |
| NO.2 | 20.00 | 5.00 | 5.84 | 116.70 | | | | | | | | | |
| NO.3 | 20.00 | 5.44 | 5.22 | 104.40 | | | | | | | | | |
| NO.4 | 20.00 | 5.28 | 5.36 | 107.20 | | | | | | | | | |
| NO.5 | 20.00 | 5.25 | 5.27 | 105.30 | | | | | | | | | |
| NO.6 | 20.00 | 5.19 | 5.22 | 104.40 | | | | | | | | | |
| NO.7 | 20.00 | 5.30 | 5.25 | 104.90 | | | | | | | | | |
| NO.8 | 20.00 | 5.27 | 5.29 | 105.70 | | | | | | | | | |
| NO.9 | 20.00 | 5.46 | 5.37 | 107.30 | | | | | | | | | |
| NO.10 | 20.00 | 5.29 | 5.38 | 107.50 | | | | | | | | | |
| NO.11 | 20.00 | 5.13 | 5.21 | 104.20 | | | | | | | | | |
| NO.12 | 20.00 | 5.27 | 5.20 | 104.00 | | | | | | | | | |
| NO.13 | 20.00 | 5.20 | 5.24 | 104.70 | | | | | | | | | |
| NO.14 | 20.00 | 5.38 | 5.29 | 105.80 | | | | | | | | | |
| NO.15 | 20.00 | 5.36 | 5.37 | 107.40 | | | | | | | | | |
| NO.16 | 20.00 | 5.33 | 5.35 | 106.90 | | | | | | | | | |
| NO.17 | 20.00 | 5.38 | 5.36 | 107.10 | | | | | | | | | |
| 合計 | | | | 1825.30 | | | | | | | | | |

舗装工数量計算書

| 測点 | 距離 (m) | 車道切削オーバーレイ(3cm) | | | | | | | | | | | |
|------------|-----------|-----------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO.17 | | 5.38 | | | | | | | | | | | |
| NO.18 | 20.00 | 5.50 | 5.44 | 108.80 | | | | | | | | | |
| NO.19 | 20.00 | 5.58 | 5.54 | 110.80 | | | | | | | | | |
| NO.20 | 20.00 | 6.11 | 5.85 | 116.90 | | | | | | | | | |
| NO.21 | 20.00 | 5.24 | 5.68 | 113.50 | | | | | | | | | |
| NO.22 | 20.00 | 5.40 | 5.32 | 106.40 | | | | | | | | | |
| NO.23 | 20.00 | 6.15 | 5.78 | 115.50 | | | | | | | | | |
| NO.24 | 20.00 | 6.03 | 6.09 | 121.80 | | | | | | | | | |
| NO.25 | 20.00 | 5.71 | 5.87 | 117.40 | | | | | | | | | |
| NO.26 | 20.00 | 5.96 | 5.84 | 116.70 | | | | | | | | | |
| NO.26+17.7 | 17.70 | 5.58 | 5.77 | 102.13 | | | | | | | | | |
| NO.27 | 2.30 | 5.49 | 5.54 | 12.73 | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 小計 | | | | 1142.66 | | | | | | | | | |
| 合計 | | | | 2967.96 | | | 0.00 | | | 0.00 | | | |

舗装工数量計算書

| 測点 | 距離 (m) | 不陸修正 | | | 車道表層(5cm) | | | | | | | | |
|--------------|-----------|-------|------|---------------------|-----------|------|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO. 0 - 0.6 | | 0.00 | | | 0.00 | | | | | | | | |
| NO. 0 | 0.60 | 1.68 | 0.84 | 0.50 | 1.68 | 0.84 | 0.50 | | | | | | |
| NO. 0 + 1.1 | 1.10 | 5.03 | 3.36 | 3.69 | 5.03 | 3.36 | 3.69 | | | | | | |
| NO. 0 + 1.1 | 0.00 | 5.58 | | | 5.58 | | | | | | | | |
| NO. 0 + 2.4 | 1.30 | 9.61 | 7.60 | 9.87 | 9.61 | 7.60 | 9.87 | | | | | | |
| NO. 0 + 7.9 | 5.50 | 3.97 | 6.79 | 37.35 | 3.97 | 6.79 | 37.35 | | | | | | |
| NO. 1 | 12.10 | 2.79 | 3.38 | 40.90 | 2.79 | 3.38 | 40.90 | | | | | | |
| NO. 2 | 20.00 | 2.65 | 2.72 | 54.40 | 2.65 | 2.72 | 54.40 | | | | | | |
| NO. 3 | 20.00 | 3.06 | 2.86 | 57.10 | 3.06 | 2.86 | 57.10 | | | | | | |
| NO. 3 + 10.6 | 10.60 | 2.99 | 3.03 | 32.07 | 2.99 | 3.03 | 32.07 | | | | | | |
| NO. 3 + 10.6 | 0.00 | 3.49 | | | 3.49 | | | | | | | | |
| NO. 4 | 9.40 | 3.26 | 3.38 | 31.73 | 3.26 | 3.38 | 31.73 | | | | | | |
| NO. 4 + 10.0 | 10.00 | 3.03 | 3.15 | 31.45 | 3.03 | 3.15 | 31.45 | | | | | | |
| NO. 4 + 10.0 | 0.00 | 3.38 | | | 3.38 | | | | | | | | |
| NO. 4 + 17.5 | 7.50 | 3.09 | 3.24 | 24.26 | 3.09 | 3.24 | 24.26 | | | | | | |
| NO. 4 + 17.5 | 0.00 | 3.59 | | | 3.59 | | | | | | | | |
| NO. 5 | 2.50 | 3.35 | 3.47 | 8.68 | 3.35 | 3.47 | 8.68 | | | | | | |
| NO. 6 | 20.00 | 3.49 | 3.42 | 68.40 | 3.49 | 3.42 | 68.40 | | | | | | |
| NO. 6 + 7.4 | 7.40 | 4.32 | 3.91 | 28.90 | 4.32 | 3.91 | 28.90 | | | | | | |
| 小計 | | | | 429.29 | | | 429.29 | | | | | | |

(須知鍋倉線)

数計-01

舗装工数量計算書

| 測点 | 距離 (m) | 不陸修正 | | | 車道表層(5cm) | | | | | | | | |
|--------------|-----------|-------|------|---------------------|-----------|------|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO. 6 + 7.4 | | 4.32 | | | 4.32 | | | | | | | | |
| NO. 6 + 10.0 | 2.60 | 5.34 | 4.83 | 12.56 | 5.34 | 4.83 | 12.56 | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 小計 | | | | 12.56 | | | 12.56 | | | | | | |
| 合計 | | | | 441.84 | | | 441.84 | | | | | | |

As 舗装取壊工数量計算書

| 測点 | 距離 (m) | As舗装取壊(t=5cm) | | | | | | | | | | | |
|--------------|-----------|---------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO. 0 - 0.6 | | 0.00 | | | | | | | | | | | |
| NO. 0 | 0.60 | 1.68 | 0.84 | 0.50 | | | | | | | | | |
| NO. 0 + 1.1 | 1.10 | 5.03 | 3.36 | 3.69 | | | | | | | | | |
| NO. 0 + 1.1 | 0.00 | 5.58 | | | | | | | | | | | |
| NO. 0 + 2.4 | 1.30 | 9.61 | 7.60 | 9.87 | | | | | | | | | |
| NO. 0 + 7.9 | 5.50 | 3.97 | 6.79 | 37.35 | | | | | | | | | |
| NO. 1 | 12.10 | 2.79 | 3.38 | 40.90 | | | | | | | | | |
| NO. 2 | 20.00 | 2.65 | 2.72 | 54.40 | | | | | | | | | |
| NO. 3 | 20.00 | 3.06 | 2.86 | 57.10 | | | | | | | | | |
| NO. 3 + 10.6 | 10.60 | 2.99 | 3.03 | 32.07 | | | | | | | | | |
| NO. 3 + 10.6 | 0.00 | 3.49 | | | | | | | | | | | |
| NO. 4 | 9.40 | 3.26 | 3.38 | 31.73 | | | | | | | | | |
| NO. 4 + 10.0 | 10.00 | 3.03 | 3.15 | 31.45 | | | | | | | | | |
| NO. 4 + 10.0 | 0.00 | 3.38 | | | | | | | | | | | |
| NO. 4 + 17.5 | 7.50 | 3.09 | 3.24 | 24.26 | | | | | | | | | |
| NO. 4 + 17.5 | 0.00 | 3.59 | | | | | | | | | | | |
| NO. 5 | 2.50 | 3.35 | 3.47 | 8.68 | | | | | | | | | |
| NO. 6 | 20.00 | 3.49 | 3.42 | 68.40 | | | | | | | | | |
| NO. 6 + 7.4 | 7.40 | 4.32 | 3.91 | 28.90 | | | | | | | | | |
| 小計 | | | | 429.29 | | | | | | | | | |

(須知鍋倉線)

数計-04

As 舗装取壊工数量計算書

| 測点 | 距離 (m) | As舗装取壊(t=5cm) | | | | | | | | | | | |
|--------------|-----------|---------------|------|---------------------|-------|----|---------------------|-------|----|---------------------|-------|----|---------------------|
| | | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) | 長さ(m) | 平均 | 数量(m ²) |
| NO. 6 + 7.4 | | 4.32 | | | | | | | | | | | |
| NO. 6 + 10.0 | 2.60 | 5.34 | 4.83 | 12.56 | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 小計 | | | | 12.56 | | | | | | | | | |
| 合計 | | | | 441.84 | | | | | | | | | |

22. 092
